ARE YOU READY FOR INSTALLATION?

In order to improve our service level and provide our clients with the best timing to schedule their installations, please take note of the following common issues and challenges for completing installations on schedule.

HOUSE STILL BEING FRAMED





House still in framing stage

NO INSULATION IN CHASE



No insulation in chase on exterior walls

FRAMING COMPLETE





House framed and wrapped

CHASE INSULATED



Insulation and air barrier installed









ARE YOU READY FOR YOUR INSTALLATION?

CHASE NOT BANDED



Chase not banded

NO ACCESS



No access to fireplace area

CHASE BANDED CORRECTLY



Chase banded correctly

APPROVED ACCESS



Fireplace installed

In order to improve our service level and provide our clients with the best timing to schedule their installations, please take note of the following common issues and challenges for completing installations on schedule.


SURROUNDS

SHEETROCK NOT INSTALLED




Sheetrock not installed

SHEETROCK INSTALLED



Sheetrock complete

OPENING CLEARANCES NOT MET



Trim built mantel does not meet fireplace opening clearances

SURROUND COMPLETE



Surround complete

CR Construction Resources

START-UPS



Gas and power need to be turned on



Not enough clearance to mantel



Other trades blocking access



Surround needs to be complete prior to start up



Job ready